

# Geotechnical Evaluation Report

US Highway 85 Intersection Improvements  
From Near US 2 and US 85 Junction north to Williams County Road 4  
Williams County, North Dakota  
SOIA-7-085(092)183, PCN 20208

*Prepared for*

**SRF Consulting Group, Inc.**

## Professional Certification:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Registered Professional Engineer under the laws of the State of North Dakota.

  
Ezra Ballinger, PE

Associate Principal/Project Engineer

Registration Number: PE-7328

April 30, 2013



Project FA-12-00359

Braun Intertec Corporation

April 30, 2013

Project FA-12-00359

Mr. Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza, Suite 226  
One North 2<sup>nd</sup> Street  
Fargo, ND 58102

Re: Geotechnical Evaluation Report (Interim Report)  
US Highway 85 Intersection Improvements  
From Near US 2 and US 85 Junction north to Williams County Road 4  
SOIA-7-085(092)183, PCN 20208  
Williams County, North Dakota

Dear Mr. Bach:

We are pleased to present this DRAFT Geotechnical Evaluation Report for the proposed construction of a US Highway 85 bypass around the northwest side of Williston, North Dakota in Williams County. Per your request, we are submitting an interim report addressing the southern 2 ½ miles of the project from the start of the project about ½ mile south of the intersection between US Highway 85 and US Highway 2 north to the intersection between 52<sup>nd</sup> Street NW and 141<sup>st</sup> Avenue NW. A report for the entirety of the project (including the portion discussed herein) will be prepared once drilling has been completed this spring. This project was completed in accordance with our proposal dated February 25, 2013.

In the Appendix of this report we present the Linear Soils Report which summarizes the results of laboratory testing in borings along the proposed route. The Appendix also contains the Boring Logs, Grain Size Accumulation Curves and Proctors. This information is being provided to SRF Consulting Group, Inc. (SRF) and the North Dakota Department of Transportation's (NDDOT) Construction Division, Materials and Research Division, and the Williston District to assist in the roadway design and determination of quantities.

Thank you for making Braun Intertec your geotechnical consultant for this project. If you have questions about this report, or if there are other services that we can provide in support of our work to date, please contact Ezra Ballinger by phone at 701.232.8701 or by email at [eballinger@braunintertec.com](mailto:eballinger@braunintertec.com).

Sincerely,

BRAUN INTERTEC CORPORATION



Ezra Ballinger, PE

Associate Principal/Project Engineer



Steven P. Nagle, PE

Principal Engineer/Vice President

# Table of Contents

Description	Page
A. Introduction.....	1
A.1. Project Description .....	1
A.2. Purpose.....	1
A.3. Scope of Services .....	2
B. Results .....	3
B.1. Borings.....	3
B.2. Geology.....	3
B.3. Site Reconnaissance .....	4
B.4. Soil Classification and Comments.....	5
B.5. Groundwater .....	6
C. Analyses and Recommendations .....	7
C.1. Proposed Construction.....	7
C.2. Treatment of Organic Soils.....	7
C.3. Subgrade Preparation .....	8
C.4. Subcutting .....	8
C.5. Subgrade Drainage .....	8
C.6. Unsuitable Materials .....	8
C.7. Settlement.....	9
C.7.a. Foundation Soils .....	9
C.7.b. Settlement of Embankment Fill.....	9
C.8. Backslopes .....	9
D. Construction .....	10
D.1. Excavation .....	10
D.2. Testing.....	10
E. Procedures.....	10
E.1. Borings.....	10
E.2. Material Classification and Testing .....	10
E.2.a. Visual and Manual Classification .....	10
E.2.b. Laboratory Testing .....	11
E.3. Groundwater Measurements.....	11
F. Qualifications.....	11
F.1. Variations in Subsurface Conditions.....	11
F.1.a. Material Strata .....	11
F.1.b. Groundwater Levels .....	11
F.2. Continuity of Professional Responsibility.....	12
F.2.a. Plan Review .....	12
F.2.b. Construction Observations and Testing .....	12



## Table of Contents (continued)

Description	Page
F.3. Use of Report.....	12
F.4. Standard of Care.....	12

### Appendix

Boring Location Sketches  
Linear Soils Report  
Log of Boring Sheets  
Descriptive Terminology  
Grain Size Accumulation Curves  
Proctor Test Results

## **A. Introduction**

### **A.1. Project Description**

The North Dakota Department of Transportation (NDDOT) is planning the construction of a bypass route for US Highway 85 in Williams County around the northwest side of Williston, North Dakota. The selected route will use a combination of existing county or township roads and undeveloped land. The route will proceed northward for about ½ mile from the junction between US Highway 85 and US Highway 2, then northwest to 141<sup>st</sup> Avenue Northwest (NW), north for about 1 mile along 141<sup>st</sup>, then northwest to 142<sup>nd</sup> Avenue NW, north along 142<sup>nd</sup> for about 3 miles, then east along 56<sup>th</sup> Street NW for 1 mile, then northeast to 57<sup>th</sup> Street NW, then east along 57<sup>th</sup> for 4 miles to its junction with US Highway 2 and US Highway 85 north of Williston. This project has been given NDDOT project number SOIA-7-085(092)183, PCN 20208.

The proposed roadway will typically be a four-lane median divided highway. Based on the preliminary plan and profile for the route, the majority of the project will involve cuts or fills of less than 5 feet, with isolated locations, especially in the northern half of the project where grade changes of 10 to 20 feet are planned.

Two new interchanges will also be constructed – one at the north end and one at the south end. In addition a new box culvert will be constructed where 142<sup>nd</sup> Avenue NW crosses Sand Creek just south of 56<sup>th</sup> Street NW.

The scope of our geotechnical evaluation is to provide SRF and the NDDOT with a linear soils survey for the route, an evaluation of the settlement potential under deep fills, recommendations for the new box culvert at Sand Creek and an evaluation of potential borrow sources. It is our understanding that the pavement section will be determined by the NDDOT and that the NDDOT will also be performing the drilling and geotechnical design of the interchanges at the north and south ends of the project.

### **A.2. Purpose**

The purpose of this geotechnical evaluation is to assist SRF and the NDDOT with the design of the project.

### **A.3. Scope of Services**

We submitted a proposal to Mr. Eric Bach of SRF on February 25, 2013. Our scope of services in the proposal consisted of the following tasks and subtasks:

- Engineering and Project Management
  - Develop project scope,
  - Site reconnaissance,
  - Prepare drilling instructions/call in utility locates,
  - Drilling oversight;
  - Traffic control,
  - Oversee laboratory testing,
  - Prepare boring logs,
  - Roadway design with regard to the anticipated fills,
  - Attend design meetings/conference calls,
  - Prepare a draft geotechnical report,
  - Prepare final geotechnical report, and
  - Overall project management of drilling, laboratory testing, and engineering.
- Drilling
  - Drill 2 standard penetration test borings to an average depth of 40 feet for the box culvert crossing at Sand Creek,
  - Drill 140 power auger borings to an average depth of 15 feet at approximately 500 feet spacings along the proposed route,
  - Drill 24 power auger borings to an average depth of 25 feet for borrow areas, and
  - Stake boring locations and coordinate with utility companies to locate buried utilities.
- Laboratory Testing
  - Conduct an average of 12 moisture contents, one modified Proctor, one Atterberg limit, and one grain size analysis test for the structure borings,
  - Conduct an average of 13 moisture contents, one modified Proctor, one Atterberg limit, and one grain size analysis test for each of the roadway borings, and
  - Conduct and average of 13 moisture contents, 1 ½ modified Proctors, 1 ½ Atterberg limits, and 1 ½ grain size analysis tests for each of the borrow borings.

Our scope of work is still ongoing and may be modified as the project progresses.

## **B. Results**

### **B.1. Borings**

Log of Boring sheets for our test borings are included in the Appendix. The logs identify and describe the geologic materials that were penetrated, and present the results of penetration resistance tests (if any) performed within them, laboratory tests performed on samples retrieved from them, and groundwater measurements. The roadway borings for this project have been numbered sequentially beginning with LSS-01 at the south end of the project and proceeding northward. This interim report addresses borings LSS-01 through LSS-30.

Boring LSS-07 was originally staked and planned to be performed near the center of the existing intersection between US Highway 85 and US Highway 2, however, due to the need for extensive traffic control and safety concerns, as well as buried utilities, that boring was not performed and a suitable offset location was not identified. Boring LSS-09 was originally planned to be advanced about 1000 feet north of the existing US Highway 2 and US Highway 85 intersection on property currently controlled by Cal Frac. However, when we visited the site on separate occasions our drillers were not able to find anyone who would grant access to the property. The majority of our borings were performed within about 12 feet of the proposed roadway centerline except where utilities or access prevented access. The coordinates of the drilled locations are provided on the attached boring logs.

Strata boundaries were inferred from changes in the auger cuttings. In the deeper borings sampling was not performed continuously and the strata boundary depths are only approximate. The boundary depths likely vary away from the boring locations, and the boundaries themselves may also occur as gradual rather than abrupt transitions.

### **B.2. Geology**

A review of geologic information in the vicinity of the site indicates that the soils are glacial till along the majority of the project, and all of the southern 2 ½ miles. Specifically, "Plate 1. Geologic Map of Williams County, North Dakota" (North Dakota Geologic Survey and North Dakota State Water Commission, Bulletin 48, County Groundwater Studies 9, Plate 1, undated) indicates the soils consist primarily of sheet moraine composed of till (an unsorted mixture of gravel, sand, silt, clay and occasional boulders).

For the project, the predominant soil type encountered was A-6 soil.

### **B.3. Site Reconnaissance**

We have visited the site on numerous occasions during 2012 in conjunction with our Phase I Environmental Site Assessment for the project. We also drove as much of it as we could in order to note the site terrain and evaluate potential drilling issues on the project. The topography along the alignment was typically gently undulating, with some areas near the northern portion of the project where the hills were steeper. For the southern 2 ½ miles that are specifically addressed by this report, the first ½ mile of the project is along the existing Highway 85 alignment south of the intersection with US Highway 2. The next ½ mile proceeds north through Cal-Frac and other industrial property. The proposed route then proceeds northwest for about ¾ mile to the existing County Road 4 alignment where it turns northward along that alignment.

The ditches along US Highway 85 south of Highway 2 were about 2 to 5 feet deep and were covered in snow at the time of our drilling. For the portion of the project that proceeds north and then northwest through the industrial property over to County Road 4, we noted that the roadway alignment appeared to have been rough graded last fall. A few inches of snow was typically present on the ground in the area. A typical view of this portion of the project at the time of our drilling is shown in Figure 1 below. As noted above, we were not able to access the Cal-Frac property immediately north of US Highway 2 because it was gated and blocked off and we were unable to find personnel that would allow us to access the property. Where the proposed alignment follows the existing County Road 4 alignment, we noted that the ditches contained ice, snow, cattails, and were several feet below the roadway centerline in many areas. The ditches, in-slopes and back-slopes were vegetated with native grasses and shrubs.

**Figure 1. Site Conditions near Station 9710+00 during drilling**



#### **B.4. Soil Classification and Comments**

For the portion of the project addressed by this interim report, we collected a total of 28 bulk samples and 290 moisture content samples from the flight auger. The borings for the linear soils survey were extended to depths of 5 to 20 feet depending on the amount of cut or fill anticipated at the location.

The results of our laboratory testing for the linear soils survey are shown in Tables 1 and 2 below and on the boring logs and laboratory results sheets, and Linear Soils Report which are provided in the Appendix.

**Table 1. Summary of Classification, Moisture Content, and Maximum Dry Unit Weight Testing for Roadway Borings**

AASHTO Classifications	Quantity	In Place Moisture Range (%)		In Place Moisture Average (%)	AASHTO T-180 Optimum Moisture Average (%)	AASHTO T-180 Maximum Dry Unit Weight Average (pcf)
		Min	Max			
A-1-b	1	5	9	7	5	138
A-2-4	2	13	18	16.1	6	135.5
A-2-6	2	12	19	14.8	6.5	134.5
A-6	19	4	26	11.9	9.2	130.2
A-7-6	4	9	19	14.4	11.0	124.5

**Table 2. Summary of Atterberg Limits Testing**

AASHTO Classifications	Quantity	Liquid Limit Range (%)		Liquid Limit Average (%)	Plastic Limit Range (%)		Plastic Limit Average (%)	Plastic Index Range		Plastic Index Average
		Min	Max		Min	Max		Min	Max	
A-1-b	1	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>	NP <sup>1</sup>
A-2-4	2	22	23	23	14	14	14	8	9	9
A-2-6	2	24	28	26	13	13	13	11	15	13
A-6	19	25	40	34	10	16	13	13	27	20
A-7-6	4	41	44	43	13	14	14	27	31	29

1. NP indicates the sample tested was Non-Plastic.

As can be seen in Table 1, the majority of the soils encountered in the linear soils survey borings were generally 2 to 10 percent wet of their optimum moisture contents as determined by AASHTO T-180. The predominant soils (A-6) were, on the average, about 2 ½ percent over their optimum moisture content. Depending on the time of construction, we anticipate the in place moisture contents are likely to be higher during spring thaw and after heavy rain events.

The soils encountered in those borings are considered moderately to highly frost-susceptible. The soils classified as A-6 and A-7-6 soils are generally considered fair to poor subgrade materials. A group index of 20 or greater indicates very poor subgrade materials. Of the 23 soils that were classified as A-6 or A-7-6 materials, all of them had a group index less than 20 (ranged from 3 to 20) and the average group index was 10.

## B.5. Groundwater

Groundwater was not observed in any of the linear soils survey borings performed to date. The observation periods were relatively short for all of the borings and water can be anticipated in other locations at the time of construction. In addition, seasonal and annual fluctuations in groundwater levels should be anticipated. Elevated water levels should be anticipated following spring thaw and periods of heavy precipitation.

## **C. Analyses and Recommendations**

### **C.1. Proposed Construction**

We have been provided with and reviewed preliminary plan and profile drawings for this project prepared by SRF in March 2013. For the portion of the project south of US Highway 2, the existing Highway 85 roadway may be widened and the intersection between Highway 2 and Highway 85 will be modified. Proceeding north from the existing US Highway 2 intersection, the new alignment will be an undivided or median divided highway having 2 to 4 lanes in either direction through the heavy industrial and developed area within about ½ mile north of US Highway 2.

From approximate Station 9735+00 (about ½ mile north of US Highway 2) to the north, the proposed roadway will be a 4 lane, median divided roadway that will also include a frontage road on either side. Several intersections will be created where the roadway will widen to accommodate one or more turning lanes in each direction. Near Station 9770+00 and continuing north to the end of the segment covered by this interim report, the proposed alignment coincides roughly with the existing alignment of County Road 4.

Based on the profile of the roadway we've reviewed, the vertical alignment of the proposed route will generally involve cuts or fills of less than 5 feet except for a couple of isolated areas near Stations 9765+00 to 9785+00, Station 9800+00 and Station 9810+00 where fills of up to about 8 feet at centerline are planned.

The pavement section for the new roadway will be developed by the NDDOT. We understand that all work on the site will be performed in accordance with NDDOT Standard Specifications.

### **C.2. Treatment of Organic Soils**

Organic soils are present in the ditches for the portions of the alignment along existing roads and also in the entire roadway area where the route will involve entirely new construction. We recommend that all vegetation, root zones and organic topsoils be removed prior to subgrade preparation and placement of new fill in these areas. After the removal of organics, the subgrade should be prepared as indicated in Section C.3. Organic soils that are removed should not be reused as embankment fill; however they could be stockpiled and may be used as dressing on the new embankment slopes.



### **C.3. Subgrade Preparation**

After vegetation and topsoils have been removed, we recommend 12 inches of subgrade preparation in cut areas, and in fill areas where less than 18 inches of fill will be placed. In fill areas where greater than 18 inches of fill will be placed, it is not necessary to perform subgrade preparation beyond topsoil stripping. Subgrade preparation should comply with NDDOT Specification 230.02 B.2 (Type A).

Compaction control for subgrade preparation should be in accordance with AASHTO T-180 and Specification 203.02G Type A.

If unsuitable soils are present below the topsoil, scarification and drying or overexcavation and replacement of the unsuitable soils could be considered.

### **C.4. Subcutting**

Based on the conditions encountered in our borings, we do not anticipate that subcutting will be necessary along the majority of the project. Where localized soft spots or unsuitable soils are encountered during subgrade preparation we recommend that subcutting of the soils be performed as necessary and in accordance with NDDOT Specification 203.02 C.

### **C.5. Subgrade Drainage**

Due to predominantly clay soils with more than 20 percent of their particles passing a #200 sieve, we recommend that drainage be provided for aggregate base placed over the on-site soils. Drainage should be provided by sloping the subgrade and daylighting the aggregate base to the shoulders. Water should not be allowed to infiltrate the clay subgrade but instead flow down the in-slopes and be collected and routed through the ditches and culverts on either side of the road.

### **C.6. Unsuitable Materials**

Based on the soils encountered in our borings, we anticipate that the soils encountered in excavations for the project will be suitable for construction of the roadway embankment. As discussed in Section C.2, organic soil deposits should not be used as embankment fill. We recommend that imported soils used as borrow be similar to the existing subgrade soils. Any soils encountered or imported that cannot be moisture conditioned and compacted according to the recommendations of this report should not be used.

## **C.7. Settlement**

Settlement will occur due to compression of the soils underlying the new roadway embankments (the foundation soils), as well as settlement of the embankment fill itself.

### **C.7.a. Foundation Soils**

Along the majority of the alignment we anticipate foundation soil settlements of less than 1 inch will be realized. The settlements will be greatest where the new fill is the thickest under the roadway and lessen where the amount of fill typically decreases along the in-slope away from the roadway. Where fills of 5 to 8 feet are planned near Stations 9765+00 to 9785+00, Station 9800+00 and Station 9810+00, we anticipate that settlement of about 1 ½ to 2 inches may be realized under the center of the roadway. The majority of the foundation soil settlement along the alignment is likely to occur within a few weeks to two months after construction of the new embankment.

### **C.7.b. Settlement of Embankment Fill**

When fill is placed, it will compress under its own weight, resulting in settlement. In clean sand soils, this settlement occurs rapidly (typically during construction), however, with clayey soils, this settlement occurs over many years. We anticipate that the majority of the soils used as embankment fill for this project will be clayey. We estimate that the total settlement of embankment fill (whether sand or clay) will be less than 1 inches for new embankments up to 8 feet thick.

## **C.8. Backslopes**

Based on experience with similar projects, we have assumed that where necessary the design cross sections will include cutting the existing soil back to a 4H:1V (Horizontal:Vertical) slope outside of the ditches. We understand that the NDDOT would prefer to use 4:1 backslopes wherever possible. If cases exist where it is not possible to use a 4:1, a 3:1 back-slope may be adequate from a stability standpoint, however, site specific evaluations should be performed for any areas under considerations for steepening beyond a 4:1.

We recommend that for any slopes greater than 20 feet tall, benches about 10 feet wide be constructed no more than 20 vertical feet apart to reduce the potential for erosion due to water flowing down the slope face. We also recommend that the back-slopes be planted with native grasses/shrubs, where possible, as a further protection against erosion. We anticipate that excavation can be performed with typical excavation equipment.

## **D. Construction**

### **D.1. Excavation**

Bedrock that impeded our drilling equipment was not encountered in our borings; therefore it is our opinion that the soils in the borings can be excavated with standard equipment such as scrapers, earth movers and backhoes. Depending on the time of construction, the subgrades may be excessively wet. It may be necessary to limit the activities of rubber-tired equipment directly on the embankment until the soils are dried.

### **D.2. Testing**

We recommend density testing of backfill and fill placed for the roadway. As indicated above, we recommend the use of AASHTO T180. The testing frequency should follow NDDOT requirements.

## **E. Procedures**

### **E.1. Borings**

The linear soils survey borings were drilled with a truck-mounted core and auger drill equipped with power auger. The borings were performed by advancing the auger at 1- or 2-foot intervals and “dead-pulling” the auger to collect moisture content samples off of the auger at 1-foot spacings. A bulk sample of the soil encountered near the anticipated bottom of the aggregate base was collected from the auger after moisture content samples were collected. Sample intervals and corresponding depths are shown on the boring logs.

### **E.2. Material Classification and Testing**

#### **E.2.a. Visual and Manual Classification**

The geologic materials encountered were visually and manually classified in accordance with ASTM Standard Practice D 2488. A chart explaining the classification system is attached. Samples were placed in jars or bags and returned to our facility for review and storage.

### **E.2.b. Laboratory Testing**

The results of the laboratory tests performed on geologic material samples are noted on or follow the appropriate attached exploration logs. The tests were performed in accordance with AASHTO procedures.

### **E.3. Groundwater Measurements**

The drillers checked for groundwater as the borings were advanced, and again after auger withdrawal. The boreholes were then backfilled.

## **F. Qualifications**

### **F.1. Variations in Subsurface Conditions**

#### **F.1.a. Material Strata**

Our evaluation, analyses and recommendations were developed from a limited amount of site and subsurface information. It is not standard engineering practice to retrieve material samples from exploration locations continuously with depth, and therefore strata boundaries and thicknesses must be inferred to some extent. Strata boundaries may also be gradual transitions, and can be expected to vary in depth, elevation and thickness away from the exploration locations.

Variations in subsurface conditions present between exploration locations may not be revealed until additional exploration work is completed, or construction commences. If any such variations are revealed, our recommendations should be re-evaluated. Such variations could increase construction costs, and a contingency should be provided to accommodate them.

#### **F.1.b. Groundwater Levels**

Groundwater measurements were made under the conditions reported herein, shown on the exploration logs, and interpreted in the text of this report. It should be noted that the observation periods were relatively short, and groundwater can be expected to fluctuate in response to rainfall, flooding, irrigation, seasonal freezing and thawing, surface drainage modifications and other seasonal and annual factors.

## **F.2. Continuity of Professional Responsibility**

### **F.2.a. Plan Review**

This report is based on a limited amount of information, and a number of assumptions were necessary to help us develop our recommendations. It is recommended that our firm review the geotechnical aspects of the designs and specifications, and evaluate whether the design is as expected, if any design changes have affected the validity of our recommendations, and if our recommendations have been correctly interpreted and implemented in the designs and specifications.

### **F.2.b. Construction Observations and Testing**

It is recommended that we be retained to perform observations and tests during construction. This will allow correlation of the subsurface conditions encountered during construction with those encountered by the borings, and provide continuity of professional responsibility.

## **F.3. Use of Report**

This report is for the exclusive use of the parties to which it has been addressed. Without written approval, we assume no responsibility to other parties regarding this report. Our evaluation, analyses and recommendations may not be appropriate for other parties or projects.

## **F.4. Standard of Care**

In performing its services, Braun Intertec Corporation used that degree of care and skill ordinarily exercised under similar circumstances by reputable members of its profession currently practicing in the same locality. No warranty, express or implied, is made.


## Appendix



F:\FA2012\FA1200359.dwg,01 PARTIAL\_4/10/2013 1:34:47 PM



⊕ DENOTES APPROXIMATE LOCATION OF  
STANDARD PENETRATION TEST BORING



250' 0 500'

SCALE: 1" = 500'

# BRAUN INTERTEC

11001 Hampshire Avenue So.  
Minneapolis, MN 55438  
PH. (952) 995-2000  
FAX (952) 995-2020

Base Dwg Provided By:  
SRF

SOIL BORING LOCATION SKETCH  
GEOTECHNICAL EVALUATION  
WILLISTON NW BYPASS  
SEVERAL ROUTES NW OF WILLISTON  
WILLIAMS COUNTY, NORTH DAKOTA

Project No: FA1200359	
Drawing No: FA1200359	
Scale:	1" = 500'
Drawn By:	BJB
Date Drawn:	4/10/13
Checked By:	EB
Last Modified:	4/10/13

Sheet:	Fig:
1 of 2	



SOIL BORING LOCATION SKETCH  
GEOTECHNICAL EVALUATION  
WILLISTON NW BYPASS  
SEVERAL ROUTES NW OF WILLISTON  
WILLIAMS COUNTY, NORTH DAKOTA



F:\FA\2012\FA1200359.dwg, 02 PARTIAL, 4/10/2013 1:35:00 PM

Project No:  
FA1200359

---

Drawing No:  
FA1200359

---

Scale:	1" = 500'
Drawn By:	BJB
Date Drawn:	4/10/13
Checked By:	EB
Last Modified:	4/10/13

Sheet: 2 of 2



# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701



Boring Number		LSS-001		LSS-002		LSS-003		LSS-004		LSS-005	
Northing		429505.60		429905.18		430404.71		430904.24		431403.73	
Easting		1181607.08		1181623.21		1181643.38		1181663.52		1181683.69	
Elevation		0.0		0.0		0.0		0.0		0.0	
Sample Depth		2.1' - 5'		2' - 5'		2' - 5'		2' - 5'		2.5' - 5'	
% Passing 3/8" Sieve		100		91		89		94		86	
% Passing No. 4 Sieve		94		70		69		81		70	
% Passing No. 10 Sieve		87		53		53		68		57	
% Coarse Sand (-No. 10, +No. 40)		12		9		13		12		11	
% Fine Sand (-No. 40, +No. 200)		27		23		23		23		29	
% Silt (0.075 - 0.002 mm)		40		17		13		30		13	
% Clay (<0.002 mm)		7		5		5		5		5	
% Finer than 0.02 mm		16		10		10		11		11	
Frost Group		F3		F2		F2		F2		F2	
Liquid Limit (-No. 40)		28		24		23		28		NP	
Plastic Limit (-No. 40)		13		13		14		13		NP	
Plasticity Index (-No. 40)		15		11		9		15		NP	
Soil Color		Brown		Brown		Brown		Brown		Brown	
USCS Classification		SC		SC		SC		SC		SM	
Soil Classification (AASHTO M-15)		A-6 (3)		A-2-6 (0)		A-2-4 (0)		A-2-6 (1)		A-1-b (0)	
Optimum Moisture (%)		7.0		6.0		6.0		7.0		5.0	
Maximum Dry Density (pcf)		135.0		136.0		134.0		133.0		138.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	2.0	12	2.0	13	2.0	16	2.0	15	2.0	7
		3.0	14	3.0	17	3.0	16	3.0	13	3.0	5
		4.0	10	4.0	19	4.0	16	4.0	12	4.0	9
Avg. Moisture of Sample Depth (all)		12		16		16		13		7	

# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701



Boring Number		LSS-006		LSS-008		LSS-010		LSS-011		LSS-012	
Northing		431903.26		432643.84		433640.42		434139.75		434639.32	
Easting		1181703.85		1181734.24		1181852.83		1181806.27		1181878.00	
Elevation		0.0		2087.7		2093.9		2093.9		2092.0	
Sample Depth		2.2' - 5'		1' - 10'		3' - 10'		0' - 6'		0' - 10'	
% Passing 3/8" Sieve		77		100		100		100		100	
% Passing No. 4 Sieve		62		98		96		97		95	
% Passing No. 10 Sieve		50		95		93		94		88	
% Coarse Sand (-No. 10, +No. 40)		12		12		12		8		10	
% Fine Sand (-No. 40, +No. 200)		24		26		26		22		21	
% Silt (0.075 - 0.002 mm)		11		36		36		43		38	
% Clay (<0.002 mm)		4		21		19		22		19	
% Finer than 0.02 mm		9		39		38		39		36	
Frost Group		F2		F3		F3		F3		F3	
Liquid Limit (-No. 40)		22		31		29		34		31	
Plastic Limit (-No. 40)		14		13		14		15		14	
Plasticity Index (-No. 40)		8		18		15		19		17	
Soil Color		Brown		Brown		Brown		Brown		Brown	
USCS Classification		SC		CL		CL		CL		CL	
Soil Classification (AASHTO M-15)		A-2-4 (0)		A-6 (7)		A-6 (5)		A-6 (10)		A-6 (6)	
Optimum Moisture (%)		6.0		7.0		9.0		9.0		9.0	
Maximum Dry Density (pcf)		137.0		135.0		131.0		131.0		131.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	2.0	13	1.0	12	3.0	20	0.0	8	0.0	14
		3.0	18	2.0	9	4.0	11	1.0	8	1.0	12
		4.0	18	3.0	9	5.0	9	2.0	13	2.0	13
				4.0	8	6.0	9	3.0	15	3.0	14
				5.0	13	7.0	16	4.0	17	4.0	12
				6.0	15	8.0	14	5.0	11	5.0	13
				7.0	15	9.0	14			6.0	14
				8.0	15					7.0	15
Avg. Moisture of Sample Depth (all)		16		12		13		12		14	

# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701



Boring Number		LSS-013		LSS-014		LSS-015		LSS-016		LSS-017	
Northing		435128.98		435577.16		435959.20		436324.66		436690.07	
Easting		1181754.64		1181536.53		1181215.26		1180874.06		1180532.97	
Elevation		2091.2		2088.7		2083.9		2079.1		2074.0	
Sample Depth		1' - 10'		1' - 10'		2' - 10'		3' - 10'		1' - 6'	
% Passing 3/8" Sieve		99		98		97		95		100	
% Passing No. 4 Sieve		97		96		96		93		97	
% Passing No. 10 Sieve		94		93		93		89		95	
% Coarse Sand (-No. 10, +No. 40)		7		8		8		7		8	
% Fine Sand (-No. 40, +No. 200)		21		22		22		22		21	
% Silt (0.075 - 0.002 mm)		37		38		39		35		39	
% Clay (<0.002 mm)		30		25		25		26		27	
% Finer than 0.02 mm		48		45		45		43		45	
Frost Group		F3		F3		F3		F3		F3	
Liquid Limit (-No. 40)		42		37		32		39		40	
Plastic Limit (-No. 40)		14		13		12		14		15	
Plasticity Index (-No. 40)		28		24		20		25		25	
Soil Color		Brown		Brown		Brown		Brown		Brown	
USCS Classification		CL		CL		CL		CL		CL	
Soil Classification (AASHTO M-15)		A-7-6 (16)		A-6 (12)		A-6 (9)		A-6 (12)		A-6 (14)	
Optimum Moisture (%)		10.0		9.0		9.0		9.0		11.0	
Maximum Dry Density (pcf)		126.0		129.0		133.0		131.0		125.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	1.0	12	1.0	12	2.0	8	3.0	16	1.0	12
		2.0	12	2.0	11	3.0	9	4.0	15	2.0	12
		3.0	10	3.0	16	4.0	12	5.0	11	3.0	15
		4.0	11	4.0	16	5.0	14	6.0	12	4.0	15
		5.0	14	5.0	7	6.0	14	7.0	14	5.0	15
		6.0	14	6.0	15	7.0	14	8.0	14		
		7.0	14	7.0	15	8.0	14	9.0	14		
		8.0	12	8.0	16	9.0	15				
Avg. Moisture of Sample Depth (all)		13		14		13		14		14	

# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701



Boring Number		LSS-018		LSS-019		LSS-020		LSS-021		LSS-022	
Northing		437055.53		437434.57		437881.39		438372.07		438871.65	
Easting		1180191.80		1179866.72		1179646.29		1179559.86		1179575.02	
Elevation		2074.0		2074.2		2077.0		2088.2		2094.5	
Sample Depth		1' - 10'		1' - 10'		1' - 6'		0.5' - 6'		3' - 15'	
% Passing 3/8" Sieve		96		90		99		100		99	
% Passing No. 4 Sieve		94		87		99		97		97	
% Passing No. 10 Sieve		90		82		97		92		92	
% Coarse Sand (-No. 10, +No. 40)		10		7		7		13		9	
% Fine Sand (-No. 40, +No. 200)		22		21		16		25		20	
% Silt (0.075 - 0.002 mm)		35		32		43		35		35	
% Clay (<0.002 mm)		24		23		30		20		28	
% Finer than 0.02 mm		39		37		52		38		46	
Frost Group		F3		F3		F3		F3		F3	
Liquid Limit (-No. 40)		36		34		38		25		39	
Plastic Limit (-No. 40)		14		14		16		10		12	
Plasticity Index (-No. 40)		22		20		22		15		27	
Soil Color		Brown		Brown		Brown		Brown		Brown	
USCS Classification		CL		CL		CL		CL		CL	
Soil Classification (AASHTO M-15)		A-6 (9)		A-6 (7)		A-6 (14)		A-6 (5)		A-6 (14)	
Optimum Moisture (%)		9.0		10.0		10.0		9.0		10.0	
Maximum Dry Density (pcf)		131.0		130.0		124.0		132.0		129.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	1.0	11	1.0	14	1.0	14	1.0	8	3.0	10
		2.0	9	2.0	17	2.0	9	2.0	5	4.0	10
		3.0	14	3.0	26	3.0	7	3.0	4	5.0	11
		4.0	14	4.0	19	4.0	8	4.0	4	6.0	11
		5.0	14	5.0	15	5.0	9	5.0	6	7.0	10
		6.0	14	6.0	14					8.0	10
		7.0	15	7.0	13					9.0	10
		8.0	15	8.0	16					10.0	20
Avg. Moisture of Sample Depth (all)		14		17		9		5		12	

# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701



Boring Number		LSS-023		LSS-024		LSS-025		LSS-026		LSS-027	
Northing		439371.36		439871.12		440370.16		440869.92		441369.55	
Easting		1179588.63		1179576.81		1179547.45		1179539.35		1179555.55	
Elevation		2101.6		2105.4		2100.9		2092.1		2087.7	
Sample Depth		0.5' - 15'		2' - 7'		0.5' - 10'		0.5' - 10'		0.3' - 5'	
% Passing 3/8" Sieve		98		98		99		99		99	
% Passing No. 4 Sieve		96		95		96		97		95	
% Passing No. 10 Sieve		94		89		91		93		90	
% Coarse Sand (-No. 10, +No. 40)		6		14		8		9		10	
% Fine Sand (-No. 40, +No. 200)		19		27		19		23		22	
% Silt (0.075 - 0.002 mm)		34		31		35		34		38	
% Clay (<0.002 mm)		35		17		29		27		21	
% Finer than 0.02 mm		53		31		47		44		39	
Frost Group		F3		F3		F3		F3			
Liquid Limit (-No. 40)		44		26		40		30		37	
Plastic Limit (-No. 40)		13		13		13		11		16	
Plasticity Index (-No. 40)		31		13		27		19		21	
Soil Color		Brown		Brown		Brown		Brown		Dark Brown	
USCS Classification		CL		SC		CL		CL		CL	
Soil Classification (AASHTO M-15)		A-7-6 (19)		A-6 (3)		A-6 (14)		A-6 (8)		A-6 (10)	
Optimum Moisture (%)		11.0		8.0		10.0		9.0		11.0	
Maximum Dry Density (pcf)		127.0		137.0		129.0		132.0		123.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	1.0	16	2.0	12	1.0	13	1.0	9	1.0	10
		2.0	9	3.0	9	2.0	12	2.0	6	2.0	9
		3.0	9	4.0	10	3.0	11	3.0	7	3.0	8
		4.0	10	5.0	9	4.0	11	4.0	9	4.0	5
		5.0	9	6.0	8	5.0	11	5.0	9		
		6.0	10			6.0	10	6.0	10		
		7.0	10			7.0	11	7.0	11		
		8.0	11			8.0	12	8.0	12		
Avg. Moisture of Sample Depth (all)		11		10		11		9		8	

# Linear Report of Tests on Soil Samples

PROJECT NO.: FA-12-00359

PROJECT: Williston NW Bypass

Highway 85

Williams County, North Dakota

Braun Intertec Corporation

PO Box 485, West Fargo, ND

Phone: (701) 232-8701

**BRAUN**  
**INTERTEC**

Boring Number		LSS-028		LSS-029		LSS-030	
Northing		441869.08		442368.53		442867.99	
Easting		1179576.65		1179597.71		1179618.93	
Elevation		2106.2		2112.2		2117.9	
Sample Depth		0.3' - 10'		0.3' - 15'		0.3' - 5'	
% Passing 3/8" Sieve		99		100		99	
% Passing No. 4 Sieve		96		99		98	
% Passing No. 10 Sieve		93		96		95	
% Coarse Sand (-No. 10, +No. 40)		7		7		8	
% Fine Sand (-No. 40, +No. 200)		19		20		26	
% Silt (0.075 - 0.002 mm)		39		40		36	
% Clay (<0.002 mm)		28		30		24	
% Finer than 0.02 mm		49		50		41	
Frost Group							
Liquid Limit (-No. 40)		44		41		34	
Plastic Limit (-No. 40)		14		14		13	
Plasticity Index (-No. 40)		30		27		21	
Soil Color		Brown		Brown		Brown	
USCS Classification		CL		CL		CL	
Soil Classification (AASHTO M-15)		A-7-6 (17)		A-7-6 (16)		A-6 (9)	
Optimum Moisture (%)		12.0		11.0		9.0	
Maximum Dry Density (pcf)		122.0		123.0		126.0	
Depth (ft)  (top 8 samples)	Moisture (%)  (top 8 samples)	1.0	19	1.0	17	1.0	6
		2.0	19	2.0	17	2.0	6
		3.0	19	3.0	17	3.0	6
		4.0	18	4.0	17	4.0	9
		5.0	18	5.0	17		
		6.0	18	6.0	17		
		7.0	18	7.0	18		
		8.0	18	8.0	18		
Avg. Moisture of Sample Depth (all)		18		17		7	

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				BORING: <b>LSS-001</b>			
				LOCATION: Station 9676+00; N429505.595, E1181607.083 See Sketch.			
DRILLER: S. Wenko		METHOD: Power Auger		DATE: <b>3/25/13</b>		SCALE: <b>1" = 4'</b>	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.6	BIT	7 inches of Bituminous Surfacing.					
	AGG	18 inches of Aggregate Base.			3		
2.1					10		
	FILL	FILL: Clayey Sand, trace Gravel, brown, moist. A-6 (3) MDD = 135.0 pcf; OMC = 7.0%.			12	LL=28, PL=13, PI=15; P200=48%	
					14		
5.0					10		
		END OF BORING.					
		Bag sample collected from 2.1 to 5 feet.					
		Water not observed with 5 feet of power auger in the ground.					
		Boring then backfilled.					

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				BORING: <b>LSS-002</b>			
				LOCATION: Station 9680+00; N429905.182, E1181623.211 See Sketch.			
DRILLER: S. Wenko		METHOD: Power Auger		DATE: <b>3/25/13</b>		SCALE: <b>1" = 4'</b>	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.5	BIT	6 1/2 inches of Bituminous Surfacing.			4	LL=24, PL=13, PI=11; P200=21%	
	AGG	18 inches of Aggregate Base.			5		
2.0							
	FILL	FILL: Clayey Sand with Gravel, brown, moist. A-2-6 (0) MDD = 136.0 pcf; OMC = 6.0%.			13		
					17		
5.0					19		
		END OF BORING.					
		Bag sample collected from 2 to 5 feet.					
		Water not observed with 5 feet of power auger in the ground.					
		Boring then backfilled.					

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11



<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				<b>BORING: LSS-003</b> <b>LOCATION: Station 9685+00; N430404.711,</b> <b>E1181643.377 See Sketch.</b>			
<b>DRILLER: S. Wenko</b>		<b>METHOD: Power Auger</b>		<b>DATE: 3/25/13</b>		<b>SCALE: 1" = 4'</b>	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.6	BIT	7 inches of Bituminous Surfacing.					
2.0	AGG	17 inches of Aggregate Base.			3 6		
5.0	FILL	FILL: Clayey Sand with Gravel, brown, moist. A-2-4 (0) MDD = 134.0 pcf; OMC = 6.0%.			16  16 16	LL=23, PL=14, PI=9; P200=17%	
<p>END OF BORING.</p> <p>Bag sample collected from 2 to 5 feet.</p> <p>Water not observed with 5 feet of power auger in the ground.</p> <p>Boring then backfilled.</p>							

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				BORING: <b>LSS-004</b>			
				LOCATION: Station 9690+00; N430904.24, E1181663.52 See Sketch.			
DRILLER: S. Wenko		METHOD: Power Auger		DATE: 3/25/13		SCALE: 1" = 4'	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.5	BIT	6 1/2 inches of Bituminous Surfacing.			4	LL=28, PL=13, PI=15; P200=34%	
	AGG	17 inches of Aggregate Base.			3		
2.0					15		
	FILL	FILL: Clayey Sand with Gravel, brown, moist. A-2-6 (1) MDD = 133.0 pcf; OMC = 7.0%.			13		
5.0					12		
		END OF BORING.					
		Bag sample collected from 2 to 5 feet.					
		Water not observed with 5 feet of power auger in the ground.					
		Boring then backfilled.					

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				BORING: <b>LSS-005</b>			
				LOCATION: Station 9695+00; N431403.733, E1181683.686 See Sketch.			
DRILLER: S. Wenko		METHOD: Power Auger		DATE: <b>3/25/13</b>		SCALE: <b>1" = 4'</b>	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.5	BIT	6 1/2 inches of Bituminous Surfacing.			2	LL=NP, PL=NP, PI=NP; P200=18%	
	AGG	20 inches of Aggregate Base.			2		
2.5					7		
	FILL	FILL: Silty Sand with Gravel, fine- to coarse-grained, brown, moist. A-1-b (0) MDD = 138.0 pcf; OMC = 5.0%.			5		
5.0		END OF BORING.			9		
		Bag sample collected from 2.5 to 5 feet.  Water not observed with 5 feet of power auger in the ground.  Boring then backfilled.					

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>				<b>BORING: LSS-006</b> <b>LOCATION: Station 9700+00; N431903.262,</b> <b>E1181703.853 See Sketch.</b>			
<b>DRILLER: S. Wenko</b>		<b>METHOD: Power Auger</b>		<b>DATE: 3/25/13</b>		<b>SCALE: 1" = 4'</b>	
Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes	
0.0							
0.5	BIT	6 1/2 inches of Bituminous Surfacing.			2	LL=22, PL=14, PI=8; P200=15%	
1.0	AGG	20 inches of Aggregate Base.			3		
2.2					13		
2.5	FILL	FILL: Clayey Sand with Gravel, brown, moist. A-2-4 (0) MDD = 137.0 pcf; OMC = 6.0%.			18		
5.0		END OF BORING.			18		
(See Descriptive Terminology sheet for explanation of abbreviations)  Bag sample collected from 2.2 to 5 feet.  Water not observed with 5 feet of power auger in the ground.  Boring then backfilled.							

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-008</b>		
					LOCATION: Station 9705+00; N432643.844, E1181734.235 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2087.7	0.0						
2086.7	1.0	FILL	FILL: Poorly Graded Sand, fine- to coarse-grained, with Gravel and Scoria, wet.			18	
		CL	SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (7) MDD = 135.0 pcf; OMC = 7.0%.			12	LL=31, PL=13, PI=18; P200=57%
						9	
						9	
						8	
						13	
						15	
						15	
						15	
2077.7	10.0					15	
			END OF BORING.				
			Bag sample collected from 1 to 10 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-010</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2093.9	0.0									
2092.9	1.0	FILL	FILL: Poorly Graded Sand, with Gravel, fine- to coarse-grained, brown and gray, moist.			6				
		FILL	FILL: Sandy Lean Clay, with Gravel, brown, moist.			14				
2090.9	3.0					14				
		CL	SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (5) MDD = 131.0 pcf; OMC = 9.0%.			20	LL=29, PL=14, PI=15; P200=56%			
						11				
						9				
						9				
						16				
						14				
2083.9	10.0					14				
END OF BORING.										
Bag sample collected from 3 to 10 feet.										
Water not observed with 10 feet of power auger in the ground.										
Boring then backfilled.										

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11 (See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-011</b>		
					<b>LOCATION:</b> Station 9720+00; N434139.745, E1181806.274 See Sketch.		
<b>DRILLER:</b> J. Brooks		<b>METHOD:</b> Power Auger		<b>DATE:</b> 3/12/13		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2093.9	0.0	FILL	FILL: Sandy Lean Clay, a little Gravel, brown, moist. A-6 (10) MDD = 131.0 pcf; OMC = 9.0%.			8	LL=34, PL=15, PI=19; P200=65%
						8	
						13	
						15	
						17	
2087.9	6.0	CL	SANDY LEAN CLAY, a little Gravel, brown, moist.			11	
						13	
						11	
						15	
2083.9	10.0					15	
			END OF BORING.				
			Bag sample collected from 0 to 6 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-012</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2092.0	0.0	FILL	FILL: Sandy Lean Clay, a little Gravel, brown, moist. A-6 (6) MDD = 131.0 pcf; OMC = 9.0%.			14	LL=31, PL=14 PI=17; P200=57%			
						12				
						13				
2088.5	3.5	CL		14						
			SANDY LEAN CLAY, a little Gravel, brown, moist.			12				
						13				
						14				
						15				
						15				
2082.0	10.0					15				
			END OF BORING.  Bag sample collected from 0 to 10 feet.  Water not observed with 10 feet of power auger in the ground.  Boring then backfilled.							



NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11 (See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-013</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2091.2	0.0	CL	LEAN CLAY with SAND, trace Gravel, brown, wet.			18				
2090.2	1.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist to damp. A-7-6 (16) MDD = 126.0 pcf; OMC = 10.0%.			12	LL=42, PL=14, PI=28; P200=67%			
						12				
						10				
						11				
						14				
						14				
						14				
						12				
						15				
2081.2	10.0		END OF BORING.							
			Bag sample collected from 1 to 10 feet.							
			Water not observed with 10 feet of power auger in the ground.							
			Boring then backfilled.							

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-014</b>		
					LOCATION: Station 9735+00; N435577.16, E1181536.53 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2088.7	0.0	CL					
2087.7	1.0	CL	SANDY LEAN CLAY, trace Gravel, brown, wet.			20	
		CL	SANDY LEAN CLAY, a little Gravel, brown, damp to moist. A-6 (12) MDD = 129.0 pcf; OMC = 9.0%.			12	LL=37, PL=13, PI=24; P200=63%
						11	
						16	
						16	
						7	
						15	
						15	
						16	
2078.7	10.0					17	
			END OF BORING.				
			Bag sample collected from 1 to 10 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-015</b>		
					LOCATION: Station 9740+00; N435959.198, E1181215.262 See Sketch.		
DRILLER: J. Brooks			METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2083.9	0.0	FILL	FILL: Sandy Lean Clay, trace Gravel, brown, moist.			13	
2081.9	2.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (9) MDD = 133.0 pcf; OMC = 9.0%.			10	
						8	LL=32, PL=12, PI=20; P200=63%
						9	
						12	
						14	
						14	
						14	
						14	
2073.9	10.0		END OF BORING.			15	
			Bag sample collected from 2 to 10 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-016</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2079.1	0.0	FILL				13				
			FILL: Sandy Lean Clay, trace Gravel, brown, moist.			15				
			-Organic, dark brown and black below 1 foot.			18				
2076.1	3.0	CL				16	LL=39, PL=14, PI=25; P200=61%			
			SANDY LEAN CLAY, a little Gravel, brown, moist.			15				
			A-6 (12)			11				
			MDD = 131.0 pcf; OMC = 9.0%.			12				
						14				
						14				
2069.1	10.0					14				
			END OF BORING.							
			Bag sample collected from 3 to 10 feet.							
			Water not observed with 10 feet of power auger in the ground.							
			Boring then backfilled.							

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11 (See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-017</b>		
					LOCATION: Station 9750+00; N436690.071, E1180532.972 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2074.0	0.0	CL					
2073.0	1.0	CL	SANDY LEAN CLAY, a little Gravel, brown, moist.			16	
		CL	SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (14) MDD = 125.0 pcf; OMC = 11.0%.			12	LL=40, PL=15, PI=25; P200=66%
						12	
						15	
						15	
2068.0	6.0	CL	LEAN CLAY with SAND, trace Gravel, gray, moist.			19	
						17	
						15	
2064.0	10.0					14	
			END OF BORING.				
			Bag sample collected from 1 to 6 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11  
(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-018</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2074.0	0.0	CL				13				
2073.0	1.0	CL	SANDY LEAN CLAY, with Gravel, trace organics, brown, moist.			11	LL=36, PL=14, PI=22; P200=58%			
		CL	SANDY LEAN CLAY, a little Gravel, brown, moist. A-6 (9) MDD = 131.0 pcf; OMC = 9.0%.			9				
						14				
						14				
						14				
						14				
						15				
						15				
2064.0	10.0					18				
			END OF BORING.							
			Bag sample collected from 1 to 10 feet.							
			Water not observed with 10 feet of power auger in the ground.							
			Boring then backfilled.							

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-019</b>		
					LOCATION: Station 9760+00; N437434.568, E1179866.717 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: <b>3/12/13</b>		SCALE: <b>1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2074.2	0.0	CL				12	
2073.2	1.0	CL	SANDY LEAN CLAY, trace Gravel and organics, brown, moist. SANDY LEAN CLAY, a little Gravel, brown, moist. A-6 (7) MDD = 130.0 pcf; OMC = 10.0%. -wet at 3 feet.			14	LL=34, PL=14, PI=20; P200=55%
						17	
						26	
						19	
						15	
						14	
						13	
						16	
2064.2	10.0					16	
			END OF BORING.  Bag sample collected from 1 to 10 feet.  Water not observed with 10 feet of power auger in the ground.  Boring then backfilled.				

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-020</b>		
					<b>LOCATION:</b> Station 9765+00; N437881.391, E1179646.293 See Sketch.		
<b>DRILLER:</b> J. Brooks		<b>METHOD:</b> Power Auger		<b>DATE:</b> 3/12/13		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2077.0	0.0						
2076.0	1.0	FILL	FILL: Lean Clay with Sand, trace Gravel, roots and Organics, brown, wet.			16	LL=38, PL=16, PI=22; P200=74%
		CL	LEAN CLAY with SAND, trace Gravel, brown, moist to damp. A-6 (14) MDD = 124.0 pcf; OMC = 10.0%.			14	
						9	
						7	
						8	
						9	
2071.0	6.0	CL	SANDY LEAN CLAY, a little Gravel, brown, damp.			9	
						8	
						8	
						10	
						9	
						11	
						11	
						11	
2062.0	15.0		END OF BORING.			11	
			Bag sample collected from 1 to 6 feet.				
			Water not observed with 15 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11



(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-021</b> <b>LOCATION: Station 9770+00; N438372.068,</b> <b>E1179559.86 See Sketch.</b>		
<b>DRILLER: J. Brooks</b>		<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2088.2	0.0	CL	SANDY LEAN CLAY, with Gravel, roots and Organics, brown and black, moist. (Topsoil) SANDY LEAN CLAY, trace Gravel, brown, damp. A-6 (5) MDD = 132.0 pcf; OMC = 9.0%.			15	LL=25, PL=10, PI=15; P200=55%
2087.7	0.5	CL		8			
				5			
				4			
				4			
2082.2	6.0	CL	SANDY LEAN CLAY, a little Gravel, brown and light gray, moist.			6	
				12			
				11			
				13			
				12			
				15			
				14			
2073.2	15.0		END OF BORING.  Bag sample collected from 0.5 to 6 feet.  Water not observed with 15 feet of power auger in the ground.  Boring then backfilled.			14	

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-022</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2094.5	0.0	CH	FAT CLAY, a little Gravel, brown, wet.			28				
2091.5	3.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (14) MDD = 129.0 pcf; OMC = 10.0%.			26				
						25				
						10	LL=39, PL=12, PI=27; P200=63%			
						10				
						11				
						11				
						10				
						10				
						10				
			-wet layer at 10 feet.			20				
						12				
						11				
						12				
2079.5	15.0	SP	POORLY GRADED SAND, fine-grained, trace Gravel, brown, damp.			11				
						3				
						3				
						2				
						2				
2074.5	20.0		END OF BORING.			2				
			Bag sample collected from 3 to 15 feet.							
			Water not observed with 20 feet of power auger in the ground.							
			Driller noted standing water in ditch.							
			Boring then backfilled.							

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-023</b>					
<b>DRILLER: J. Brooks</b>					<b>METHOD: Power Auger</b>		<b>DATE: 3/12/13</b>		<b>SCALE: 1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes			
2101.6	0.0									
2101.1	0.5	CL CL	LEAN CLAY with SAND, roots and Organics, trace Gravel, brown, wet. SANDY LEAN CLAY, trace Gravel, brown, moist to damp. A-7-6 (19) MDD = 127.0 pcf; OMC = 11.0%.			19	LL=44, PL=13, PI=31; P200=69%			
						16				
						9				
						9				
						10				
						9				
						10				
						10				
						11				
						10				
						10				
						11				
						11				
						11				
2086.6	15.0		END OF BORING.  Bag sample collected from 0.5 to 15 feet.  Water not observed with 15 feet of power auger in the ground.  Boring then backfilled.			11				

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-024</b>		
					LOCATION: Station 9785+00; N439871.117, E1179576.81 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2105.4	0.0	FILL	FILL: Sandy Lean Clay, trace Gravel, brown, wet.			12	LL=26, PL=13, PI=13; P200=48%
2103.4	2.0	SC	CLAYEY SAND, a little Gravel, brown, moist. A-6 (3) MDD = 137.0 pcf; OMC = 8.0%.			9	
						12	
						9	
						10	
2098.4	7.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist.			8	
						14	
2095.4	10.0		END OF BORING.			14	
			Bag sample collected from 2 to 7 feet.			13	
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-025</b>		
					LOCATION: Station 9790+00; N440370.162, E1179547.453 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2100.9	0.0	CL	SANDY LEAN CLAY, trace Gravel, roots and Organics, brown, wet. SANDY LEAN CLAY, trace Gravel, brown, moist. A-6 (14) MDD = 129.0 pcf; OMC = 10.0%.			13	LL=40, PL=13, PI=27; P200=64%
2100.4	0.5	CL				13	
						12	
						11	
						11	
						11	
						10	
						11	
						12	
						11	
2090.9	10.0		END OF BORING.  Bag sample collected from 0.5 to 10 feet.  Water not observed with 10 feet of power auger in the ground.  Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-026</b>		
					LOCATION: Station 9795+00; N440869.915, E1179539.35 See Sketch.		
DRILLER: J. Brooks		METHOD: Power Auger		DATE: 3/12/13		SCALE: 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2092.1	0.0	CL	SANDY LEAN CLAY, trace Gravel, roots and Organics, brown, wet. SANDY LEAN CLAY, trace Gravel, brown, moist to damp. A-6 (8) MDD = 132.0 pcf; OMC = 9.0%.			16	LL=30, PL=11, PI=19; P200=61%
2091.6	0.5	CL				9	
						6	
						7	
						9	
						9	
						10	
						11	
						12	
						12	
2082.1	10.0		END OF BORING.  Bag sample collected from 0.5 to 10 feet.  Water not observed with 10 feet of power auger in the ground.  Boring then backfilled.				

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-027</b>		
					<b>LOCATION:</b> Station 9800+00; N441369.552, E1179555.546 See Sketch.		
<b>DRILLER:</b> C. Elliot		<b>METHOD:</b> Power Auger		<b>DATE:</b> 3/23/13		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2087.7	0.0	CL	SANDY LEAN CLAY, with roots and organics, black, moist. SANDY LEAN CLAY, trace Gravel, dark brown, damp. A-6 (10) MDD = 123.0 pcf; OMC = 11.0%.			11	LL=37, PL=16, PI=21; P200=60%
2087.4	0.3	CL				10	
						9	
						8	
						5	
2082.7	5.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist.			14	
						13	
						15	
						15	
						16	
						18	
						18	
						18	
						17	
						18	
						18	
						18	
						18	
						17	
2067.7	20.0			END OF BORING.			
			Bag sample collected from 0.3 to 5 feet.  Water not observed with 20 feet of power auger in the ground.  Boring then backfilled.				

(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:11

(See Descriptive Terminology sheet for explanation of abbreviations)

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					BORING: <b>LSS-028</b>		
					LOCATION: Station 9805+00; N441869.078, E1179576.648 See Sketch.		
DRILLER: C. Elliot		METHOD: Power Auger		DATE: <b>3/23/13</b>		SCALE: <b>1" = 4'</b>	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2106.2	0.0	CL	SANDY LEAN CLAY, with roots and organics, black, moist. SANDY LEAN CLAY, trace Gravel, brown, moist. A-7-6 (17) MDD = 122.0 pcf; OMC = 12.0%.			19	LL=44, PL=14, PI=30; P200=67%
2105.9	0.3	CL				19	
						19	
						19	
						18	
						18	
						18	
						18	
						18	
						18	
2096.2	10.0		END OF BORING.  Bag sample collected from 0.3 to 10 feet.  Water not observed with 10 feet of power auger in the ground.  Boring then backfilled.				



(See Descriptive Terminology sheet for explanation of abbreviations)

NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:12

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-029</b>		
					<b>LOCATION:</b> Station 9810+00; N442368.53, E1179597.711 See Sketch.		
<b>DRILLER:</b> C. Elliot		<b>METHOD:</b> Power Auger		<b>DATE:</b> 3/23/13		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2112.2	0.0	CL	SANDY LEAN CLAY, with roots and organics, black, moist. SANDY LEAN CLAY, trace Gravel, brown, moist. A-7-6 (16) MDD = 123.0 pcf; OMC = 11.0%.			17	LL=41, PL=14, PI=27; P200=69%
2111.9	0.3	CL				17	
						17	
						17	
						17	
						17	
						17	
						17	
						18	
						18	
						17	
						16	
						16	
						17	
						16	
2097.2	15.0		END OF BORING.  Bag sample collected from 0.3 to 15 feet.  Water not observed with 15 feet of power auger in the ground.  Boring then backfilled.			16	

(See Descriptive Terminology sheet for explanation of abbreviations)


NDDOT LOG 00359.GPJ BRAUN.GDT 4/17/13 10:12

<b>Braun Project FA-12-00359</b> <b>Geotechnical Evaluation</b> <b>Williston NW Bypass</b> <b>Several Routes, NW of Williston</b> <b>Williams County, North Dakota</b>					<b>BORING: LSS-030</b>		
					<b>LOCATION:</b> Station 9815+00; N442867.989, E1179618.927 See Sketch.		
<b>DRILLER:</b> C. Elliot		<b>METHOD:</b> Power Auger		<b>DATE:</b> 3/23/13		<b>SCALE:</b> 1" = 4'	
Elev. feet	Depth feet	ASTM Symbol	Description of Materials (ASTM D2488 or D2487)	BPF	WL	MC %	Tests or Notes
2117.9	0.0	CL	SANDY LEAN CLAY, with roots and organics, black, moist. SANDY LEAN CLAY, trace Gravel, brown, damp. A-6 (9) MDD = 126.0 pcf; OMC = 9.0%.			7	LL=34, PL=13, PI=21; P200=60%
2117.6	0.3	CL				6	
						6	
						6	
						9	
2112.9	5.0	CL	SANDY LEAN CLAY, trace Gravel, brown, moist.			14	
						15	
						15	
						15	
2107.9	10.0		END OF BORING.			14	
			Bag sample collected from 0.3 to 5 feet.				
			Water not observed with 10 feet of power auger in the ground.				
			Boring then backfilled.				



Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests <sup>a</sup>					Soils Classification	
					Group Symbol	Group Name <sup>b</sup>
Coarse-grained Soils More than 50% retained on No. 200 sieve	Gravels More than 50% of coarse fraction retained on No. 4 sieve	Clean Gravels 5% or less fines <sup>c</sup>	$C_u \geq 4$ and $1 \leq C_c \leq 3$ <sup>c</sup>	GW	Well-graded gravel <sup>d</sup>	
			$C_u < 4$ and/or $1 > C_c > 3$ <sup>c</sup>	GP	Poorly graded gravel <sup>d</sup>	
	Gravels with Fines More than 12% fines <sup>a</sup>	Fines classify as ML or MH	GM	Silty gravel <sup>d,g</sup>		
		Fines classify as CL or CH	GC	Clayey gravel <sup>d,g</sup>		
	Sands 50% or more of coarse fraction passes No. 4 sieve	Clean Sands 5% or less fines <sup>i</sup>	$C_u \geq 6$ and $1 \leq C_c \leq 3$ <sup>c</sup>	SW	Well-graded sand <sup>h</sup>	
			$C_u < 6$ and/or $1 > C_c > 3$ <sup>c</sup>	SP	Poorly graded sand <sup>h</sup>	
		Sands with Fines More than 12% <sup>i</sup>	Fines classify as ML or MH	SM	Silty sand <sup>g,h</sup>	
			Fines classify as CL or CH	SC	Clayey sand <sup>g,h</sup>	
Fine-grained Soils 50% or more passed the No. 200 sieve	Silts and Clays Liquid limit less than 50	Inorganic	PI > 7 and plots on or above "A" line <sup>j</sup>	CL	Lean clay <sup>k,l,m</sup>	
			PI < 4 or plots below "A" line <sup>j</sup>	ML	Silt <sup>k,l,m</sup>	
		Organic	Liquid limit - oven dried	< 0.75	OL	Organic clay <sup>k,l,m,n</sup>
			Liquid limit - not dried		OL	Organic silt <sup>k,l,m,o</sup>
	Silts and clays Liquid limit 50 or more	Inorganic	PI plots on or above "A" line	CH	Fat clay <sup>k,l,m</sup>	
			PI plots below "A" line	MH	Elastic silt <sup>k,l,m</sup>	
		Organic	Liquid limit - oven dried	< 0.75	OH	Organic clay <sup>k,l,m,p</sup>
			Liquid limit - not dried		OH	Organic silt <sup>k,l,m,q</sup>
Highly Organic Soils		Primarily organic matter, dark in color and organic odor			PT	Peat

- a. Based on the material passing the 3-in (75mm) sieve.  
b. If field sample contained cobbles or boulders, or both, add "with cobbles or boulders or both" to group name.  
c.  $C_u = D_{60} / D_{10}$   $C_c = (D_{30})^2 / (D_{10} \times D_{60})$   
d. If soil contains  $\geq 15\%$  sand, add "with sand" to group name.  
e. Gravels with 5 to 12% fines require dual symbols:  
GW-GM well-graded gravel with silt  
GW-GC well-graded gravel with clay  
GP-GM poorly graded gravel with silt  
GP-GC poorly graded gravel with clay  
f. If fines classify as CL-ML, use dual symbol GC-GM or SC-SM.  
g. If fines are organic, add "with organic fines" to group name.  
h. If soil contains  $\geq 15\%$  gravel, add "with gravel" to group name.  
i. Sands with 5 to 12% fines require dual symbols:  
SW-SM well-graded sand with silt  
SW-SC well-graded sand with clay  
SP-SM poorly graded sand with silt  
SP-SC poorly graded sand with clay  
j. If Atterberg limits plot in hatched area, soil is a CL-ML, silty clay.  
k. If soil contains 10 to 29% plus No. 200, add "with sand" or "with gravel" whichever is predominant.  
l. If soil contains  $\geq 30\%$  plus No. 200, predominantly sand, add "sandy" to group name.  
m. If soil contains  $\geq 30\%$  plus No. 200 predominantly gravel, add "gravelly" to group name.  
n. PI  $\geq 4$  and plots on or above "A" line.  
o. PI < 4 or plots below "A" line.  
p. PI plots on or above "A" line.  
q. PI plots below "A" line.



Laboratory Tests

DD	Dry density, pcf	OC	Organic content, %
WD	Wet density, pcf	S	Percent of saturation, %
MC	Natural moisture content, %	SG	Specific gravity
LL	Liquid limit, %	C	Cohesion, psf
PL	Plastic limit, %	$\phi$	Angle of internal friction
PI	Plasticity index, %	qu	Unconfined compressive strength, psf
P200	% passing 200 sieve	qp	Pocket penetrometer strength, tsf

## Particle Size Identification

Boulders	over 12"
Cobbles	3" to 12"
Gravel	
Coarse	3/4" to 3"
Fine	No. 4 to 3/4"
Sand	
Coarse	No. 4 to No. 10
Medium	No. 10 to No. 40
Fine	No. 40 to No. 200
Silt	< No. 200, PI < 4 or below "A" line
Clay	< No. 200, PI $\geq 4$ and on or above "A" line

## Relative Density of Cohesionless Soils

Very loose	0 to 4 BPF
Loose	5 to 10 BPF
Medium dense	11 to 30 BPF
Dense	31 to 50 BPF
Very dense	over 50 BPF

## Consistency of Cohesive Soils

Very soft	0 to 1 BPF
Soft	2 to 3 BPF
Rather soft	4 to 5 BPF
Medium	6 to 8 BPF
Rather stiff	9 to 12 BPF
Stiff	13 to 16 BPF
Very stiff	17 to 30 BPF
Hard	over 30 BPF

## Drilling Notes

Standard penetration test borings were advanced by 3 1/4" or 6 1/4" ID hollow-stem augers unless noted otherwise. Jetting water was used to clean out auger prior to sampling only where indicated on logs. Standard penetration test borings are designated by the prefix "ST" (Split Tube). All samples were taken with the standard 2" OD split-tube sampler, except where noted.

Power auger borings were advanced by 4" or 6" diameter continuous-flight, solid-stem augers. Soil classifications and strata depths were inferred from disturbed samples augered to the surface and are, therefore, somewhat approximate. Power auger borings are designated by the prefix "B."

Hand auger borings were advanced manually with a 1 1/2" or 3 1/4" diameter auger and were limited to the depth from which the auger could be manually withdrawn. Hand auger borings are indicated by the prefix "H."

**BPF:** Numbers indicate blows per foot recorded in standard penetration test, also known as "N" value. The sampler was set 6" into undisturbed soil below the hollow-stem auger. Driving resistances were then counted for second and third 6" increments and added to get BPF. Where they differed significantly, they are reported in the following form: 2/12 for the second and third 6" increments, respectively.


**WH:** WH indicates the sampler penetrated soil under weight of hammer and rods alone; driving not required.

**WR:** WR indicates the sampler penetrated soil under weight of rods alone; hammer weight and driving not required.

**TW** indicates thin-walled (undisturbed) tube sample.

**Note:** All tests were run in general accordance with applicable ASTM standards.

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-001 DEPTH: 2.1'-5.0'

GRAVEL 13.0%  
SAND 39.0%  
SILT 40.5%  
CLAY 7.4%

CLASSIFICATION:  
A-6 (3), Brown  
CLAYEY SAND(SC)  
  
LL=28, PL=13, PI=15; P200=48%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-002 DEPTH: 2.0'-5.0'

GRAVEL 46.8%  
SAND 31.8%  
SILT 16.6%  
CLAY 4.8%

CLASSIFICATION:  
A-2-6 (0), Brown  
CLAYEY SAND with GRAVEL(SC)  
  
LL=24, PL=13, PI=11; P200=21%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-003 DEPTH: 2.0'-5.0'

GRAVEL 47.0%  
SAND 35.7%  
SILT 12.6%  
CLAY 4.7%

CLASSIFICATION:  
A-2-4 (0), Brown  
CLAYEY SAND with GRAVEL(SC)  
LL=23, PL=14, PI=9; P200=17%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-004 DEPTH: 2.0'-5.0'

GRAVEL 32.1%  
SAND 33.5%  
SILT 29.8%  
CLAY 4.6%

CLASSIFICATION:  
A-2-6 (1), Brown  
CLAYEY SAND with GRAVEL(SC)  
  
LL=28, PL=13, PI=15; P200=34%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-005 DEPTH: 2.5'-5.0'

GRAVEL	43.3%
SAND	39.0%
SILT	12.8%
CLAY	4.9%

CLASSIFICATION:  
A-1-b (0), Brown  
SILTY SAND with GRAVEL(SM)  
  
LL=NP, PL=NP, PI=NP; P200=18%



# GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
 BORING: LSS-006 DEPTH: 2.2'-5.0'

GRAVEL	49.7%
SAND	35.1%
SILT	10.9%
CLAY	4.4%

CLASSIFICATION:  
 A-2-4 (0), Brown  
 CLAYEY SAND with GRAVEL(SC)  
 LL=22, PL=14, PI=8; P200=15%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-008 DEPTH: 1.0'-10.0'

GRAVEL 5.1%  
SAND 37.9%  
SILT 35.7%  
CLAY 21.3%

CLASSIFICATION:  
A-6 (7), Brown  
SANDY LEAN CLAY(CL)  
LL=31, PL=13, PI=18; P200=57%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-010 DEPTH: 3.0'-10.0'

GRAVEL 7.2%  
SAND 37.3%  
SILT 36.4%  
CLAY 19.1%

CLASSIFICATION:  
A-6 (5), Brown  
SANDY LEAN CLAY(CL)  
LL=29, PL=14, PI=15; P200=56%

# GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**BRAUN**<sup>SM</sup>  
**INTERTEC**

**Braun Project FA-12-00359**

**Geotechnical Evaluation**

**Williston NW Bypass**

**Several Routes, NW of Williston**

**Williams County, North Dakota**

BORING: LSS-011 DEPTH: 0.0'-6.0'


GRAVEL	5.9%
SAND	29.5%
SILT	42.8%
CLAY	21.8%

CLASSIFICATION:

A-6 (10), Brown  
SANDY LEAN CLAY(CL)

LL=34, PL=15, PI=19; P200=65%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-012 DEPTH: 0.0'-10.0'

GRAVEL 11.8%  
SAND 30.8%  
SILT 38.1%  
CLAY 19.3%

CLASSIFICATION:  
A-6 (6), Brown  
SANDY LEAN CLAY(CL)  
LL=31, PL=14 PI=17; P200=57%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-013 DEPTH: 1.0'-10.0'

GRAVEL 6.0%  
SAND 26.8%  
SILT 36.8%  
CLAY 30.3%

CLASSIFICATION:  
A-7-6 (16), Brown  
SANDY LEAN CLAY(CL)  
LL=42, PL=14, PI=28; P200=67%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-014 DEPTH: 1.0'-10.0'

GRAVEL 7.1%  
SAND 29.6%  
SILT 38.1%  
CLAY 25.2%

CLASSIFICATION:  
A-6 (12), Brown  
SANDY LEAN CLAY(CL)  
LL=37, PL=13, PI=24; P200=63%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-015 DEPTH: 2.0'-10.0'

GRAVEL 6.6%  
SAND 29.9%  
SILT 38.6%  
CLAY 24.8%

CLASSIFICATION:  
A-6 (9), Brown  
SANDY LEAN CLAY(CL)  
LL=32, PL=12, PI=20; P200=63%



# GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
 BORING: LSS-016 DEPTH: 3.0'-10.0'

GRAVEL	10.8%
SAND	28.5%
SILT	34.6%
CLAY	26.1%

CLASSIFICATION:  
 A-6 (12), Brown  
 SANDY LEAN CLAY(CL)  
 LL=39, PL=14, PI=25; P200=61%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-017 DEPTH: 1.0'-6.0'

GRAVEL 5.1%  
SAND 28.5%  
SILT 39.0%  
CLAY 27.4%

CLASSIFICATION:  
A-6 (14), Brown  
SANDY LEAN CLAY(CL)  
  
LL=40, PL=15, PI=25; P200=66%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-018 DEPTH: 1.0'-10.0'

GRAVEL 10.0%  
SAND 31.6%  
SILT 34.8%  
CLAY 23.7%

CLASSIFICATION:  
A-6 (9), Brown  
SANDY LEAN CLAY(CL)  
  
LL=36, PL=14, PI=22; P200=58%

# GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**BRAUN**<sup>SM</sup>  
**INTERTEC**

**Braun Project FA-12-00359**

**Geotechnical Evaluation**

**Williston NW Bypass**

**Several Routes, NW of Williston**

**Williams County, North Dakota**

BORING: LSS-019 DEPTH: 1.0'-10.0'

GRAVEL 17.6%

SAND 27.7%

SILT 31.9%


CLAY 22.8%

CLASSIFICATION:

A-6 (7), Brown  
SANDY LEAN CLAY(CL)

LL=34, PL=14, PI=20; P200=55%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-020 DEPTH: 1.0'-6.0'

GRAVEL 3.5%  
SAND 23.0%  
SILT 43.4%  
CLAY 30.2%

CLASSIFICATION:  
A-6 (14), Brown  
LEAN CLAY with SAND(CL)  
LL=38, PL=16, PI=22; P200=74%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-021 DEPTH: 0.5'-6.0'

GRAVEL 7.8%  
SAND 37.4%  
SILT 34.5%  
CLAY 20.3%

CLASSIFICATION:  
A-6 (5), Brown  
SANDY LEAN CLAY(CL)  
LL=25, PL=10, PI=15; P200=55%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-022 DEPTH: 3.0'-15.0'

GRAVEL 7.9%  
SAND 29.1%  
SILT 35.4%  
CLAY 27.5%

CLASSIFICATION:  
A-6 (14), Brown  
SANDY LEAN CLAY(CL)  
LL=39, PL=12, PI=27; P200=63%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-023 DEPTH: 0.5'-15.0'

GRAVEL 6.2%  
SAND 24.5%  
SILT 34.1%  
CLAY 35.2%

CLASSIFICATION:  
A-7-6 (19), Brown  
SANDY LEAN CLAY(CL)  
  
LL=44, PL=13, PI=31; P200=69%



GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-024 DEPTH: 2.0'-7.0'

GRAVEL 11.2%  
SAND 40.8%  
SILT 31.1%  
CLAY 17.0%

CLASSIFICATION:  
A-6 (3), Brown  
CLAYEY SAND(SC)  
LL=26, PL=13, PI=13; P200=48%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-025 DEPTH: 0.5'-10.0'

GRAVEL 8.9%  
SAND 26.7%  
SILT 35.2%  
CLAY 29.2%

CLASSIFICATION:  
A-6 (14), Brown  
SANDY LEAN CLAY(CL)  
LL=40, PL=13, PI=27; P200=64%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-026 DEPTH: 0.5'-10.0'

GRAVEL 7.1%  
SAND 32.2%  
SILT 33.7%  
CLAY 27.0%

CLASSIFICATION:  
A-6 (8), Brown  
SANDY LEAN CLAY(CL)  
LL=30, PL=11, PI=19; P200=61%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-027 DEPTH: 0.3'-5.0'

GRAVEL 9.6%  
SAND 30.8%  
SILT 38.4%  
CLAY 21.3%

CLASSIFICATION:  
A-6 (10), Dark Brown  
SANDY LEAN CLAY(CL)  
LL=37, PL=16, PI=21; P200=60%

# GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**BRAUN**<sup>SM</sup>  
**INTERTEC**

**Braun Project FA-12-00359**

**Geotechnical Evaluation**

**Williston NW Bypass**

**Several Routes, NW of Williston**

**Williams County, North Dakota**

BORING: LSS-028 DEPTH: 0.3'-10.0'


GRAVEL	6.9%
SAND	25.7%
SILT	39.3%
CLAY	28.1%

CLASSIFICATION:

A-7-6 (17), Brown  
SANDY LEAN CLAY(CL)

LL=44, PL=14, PI=30; P200=67%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)




**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-029 DEPTH: 0.3'-15.0'

GRAVEL 3.8%  
SAND 27.0%  
SILT 39.6%  
CLAY 29.6%

CLASSIFICATION:  
A-7-6 (16), Brown  
SANDY LEAN CLAY(CL)  
LL=41, PL=14, PI=27; P200=69%

GRAIN SIZE ACCUMULATION CURVE (AASHTO)



**Braun Project FA-12-00359**  
**Geotechnical Evaluation**  
**Williston NW Bypass**  
**Several Routes, NW of Williston**  
**Williams County, North Dakota**  
BORING: LSS-030 DEPTH: 0.3'-5.0'

GRAVEL 5.1%  
SAND 34.5%  
SILT 36.1%  
CLAY 24.3%

CLASSIFICATION:  
A-6 (9), Brown  
SANDY LEAN CLAY(CL)  
LL=34, PL=13, PI=21; P200=60%

# Proctor Report

Report No: PTR:W13-000494-S1

Issue No: 1

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S1	<b>Alternate Sample ID:</b>	LSS-001; 2.1'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand (SC); A-6 (3)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-001; 2.1'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/2/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>135</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>135</b>
<b>Optimum Moisture Content (%):</b>	<b>7</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>7</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 28; PI = 15  
Percent Retained on #4 Sieve = 6.2%; Percent Passing #200 Sieve = 47.7%



# Proctor Report

Report No: PTR:W13-000494-S2

Issue No: 1

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S2	<b>Alternate Sample ID:</b>	LSS-002; 2'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand with Gravel (SC); A-2-6 (0)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-002; 2'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/2/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>136</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>136</b>
<b>Optimum Moisture Content (%):</b>	<b>6</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>6</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 24; PI = 11  
Percent Retained on #4 Sieve = 29.7%; Percent Passing #200 Sieve = 21.4%

# Proctor Report

**Report No: PTR:W13-000494-S3****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S3	<b>Alternate Sample ID:</b>	LSS-003; 2'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand with Gravel (SC); A-2-4 (0)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-003; 2'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/8/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>134</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>134</b>
<b>Optimum Moisture Content (%):</b>	<b>6</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>6</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 23; PI = 9  
Percent Retained on #4 Sieve = 30.7%; Percent Passing #200 Sieve = 17.3%

# Proctor Report

**Report No: PTR:W13-000494-S4****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S4	<b>Alternate Sample ID:</b>	LSS-004; 2'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand with Gravel (SC); A-2-6 (1)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-004; 2'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/5/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>133</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>133</b>
<b>Optimum Moisture Content (%):</b>	<b>7</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>7</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 28; PI = 15  
Percent Retained on #4 Sieve = 19.2%; Percent Passing #200 Sieve = 34.4%

# Proctor Report

**Report No: PTR:W13-000494-S5****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S5	<b>Alternate Sample ID:</b>	LSS-005; 2.5'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Silty Sand with Gravel (SM); A-1-b (0)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-005; 2.5'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/1/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>138</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>138</b>
<b>Optimum Moisture Content (%):</b>	<b>5</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>5</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
Non-Plastic  
Percent Retained on #4 Sieve = 30.2%; Percent Passing #200 Sieve = 17.7%

# Proctor Report

**Report No: PTR:W13-000494-S6****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S6	<b>Alternate Sample ID:</b>	LSS-006; 2.2'-5'
<b>Date Sampled:</b>	3/25/2013	<b>Date Submitted:</b>	3/25/2013
<b>Sampled By:</b>	Steve Wenko	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand with Gravel (SC); A-2-4 (0)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-006; 2.2'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/2/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>137</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>137</b>
<b>Optimum Moisture Content (%):</b>	<b>6</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>6</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 22; PI = 8  
Percent Retained on #4 Sieve = 37.8%; Percent Passing #200 Sieve = 15.3%

# Proctor Report

Report No: PTR:W13-000494-S8

Issue No: 1

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S8	<b>Alternate Sample ID:</b>	LSS-008; 1'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (7)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-008; 1'-10'		
<b>Tested By:</b>	Thomas Wagner	<b>Date Tested:</b>	3/19/2013

## Dry Density - Moisture Content Relationship



## Test Results

\_\_\_\_ AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>135</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>135</b>
<b>Optimum Moisture Content (%):</b>	<b>7</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>7</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 31; PI = 18  
Percent Retained on #4 Sieve = 7.2%; Percent Passing #200 Sieve = 57.0%

# Proctor Report

**Report No: PTR:W13-000494-S10****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S10	<b>Alternate Sample ID:</b>	LSS-010; 3'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (5)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-010; 3'-10'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/19/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 29; PI = 15  
Percent Retained on #4 Sieve = 5.4%; Percent Passing #200 Sieve = 55.6%



# Proctor Report

**Report No: PTR:W13-000494-S11****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S11	<b>Alternate Sample ID:</b>	LSS-011; 0'-6'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (10)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-011; 0'-6'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/19/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 34; PI = 19  
Percent Retained on #4 Sieve = 5.7%; Percent Passing #200 Sieve = 64.6%



# Proctor Report

**Report No: PTR:W13-000494-S12****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S12	<b>Alternate Sample ID:</b>	LSS-012; 0'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (6)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-012; 0'-10'		
<b>Tested By:</b>	Thomas Wagner	<b>Date Tested:</b>	3/20/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 31; PI = 17  
Percent Retained on #4 Sieve = 5.3%; Percent Passing #200 Sieve = 57.4%

# Proctor Report

**Report No: PTR:W13-000494-S13****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S13	<b>Alternate Sample ID:</b>	LSS-013; 1'-10
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-7-6 (16)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-013; 1'-10		
<b>Tested By:</b>	Matt Daavetilla	<b>Date Tested:</b>	3/20/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>126</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>126</b>
<b>Optimum Moisture Content (%):</b>	<b>10</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>10</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 42; PI = 28  
Percent Retained on #4 Sieve = 2.8%; Percent Passing #200 Sieve = 67.1%

# Proctor Report

**Report No: PTR:W13-000494-S14****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S14	<b>Alternate Sample ID:</b>	LSS-14; 1'-10
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (12)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-14; 1'-10		
<b>Tested By:</b>	Rodney Schnieder	<b>Date Tested:</b>	3/20/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
<b>Method:</b>	A
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 37; PI = 24  
Percent Retained on #4 Sieve = 4.1%; Percent Passing #200 Sieve = 63.3%

# Proctor Report

**Report No: PTR:W13-000494-S15****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S15	<b>Alternate Sample ID:</b>	LSS-15; 2'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (9)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-15; 2'-10'		
<b>Tested By:</b>	Shane Falwey	<b>Date Tested:</b>	3/20/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>133</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>133</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
<b>Method:</b>	A
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 32; PI = 20  
Percent Retained on #4 Sieve = 3.9%; Percent Passing #200 Sieve = 63.4%

# Proctor Report

**Report No: PTR:W13-000494-S16****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S16	<b>Alternate Sample ID:</b>	LSS-16; 3'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/15/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (12)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-16; 3'-10'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/19/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 39; PI = 25  
Percent Retained on #4 Sieve = 7.0%; Percent Passing #200 Sieve = 60.7%

# Proctor Report

**Report No: PTR:W13-000494-S17****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S17	<b>Alternate Sample ID:</b>	LSS-17; 1'-6'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (14)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-17; 1'-6'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/20/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>125</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>125</b>
<b>Optimum Moisture Content (%):</b>	<b>11</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>11</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 40; PI = 25  
Percent Retained on #4 Sieve = 3.2%; Percent Passing #200 Sieve = 66.4%

# Proctor Report

**Report No: PTR:W13-000494-S18****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S18	<b>Alternate Sample ID:</b>	LSS-18; 1'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (9)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-18; 1'-10'		
<b>Tested By:</b>	Thomas Wagner	<b>Date Tested:</b>	3/21/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>131</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
Method:	D
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 36; PI = 22  
Percent Retained on #4 Sieve = 6.4%; Percent Passing #200 Sieve = 58.4%



# Proctor Report

**Report No: PTR:W13-000494-S19****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S19	<b>Alternate Sample ID:</b>	LSS-019; 1'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (7)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-019; 1'-10'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/21/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>130</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>130</b>
<b>Optimum Moisture Content (%):</b>	<b>10</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>10</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 34; PI = 20  
Percent Retained on #4 Sieve = 12.8%; Percent Passing #200 Sieve = 54.7%



# Proctor Report

**Report No: PTR:W13-000494-S20****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S20	<b>Alternate Sample ID:</b>	LSS-20; 1'-6'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Lean Clay with Sand (CL); A-6 (14)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-20; 1'-6'		
<b>Tested By:</b>	Shane Falwey	<b>Date Tested:</b>	3/22/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>124</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>124</b>
<b>Optimum Moisture Content (%):</b>	<b>10</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>10</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 38; PI = 22  
Percent Retained on #4 Sieve = 1.3%; Percent Passing #200 Sieve = 73.6%

# Proctor Report

**Report No: PTR:W13-000494-S21****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S21	<b>Alternate Sample ID:</b>	LSS-21; 0.5'-6'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (5)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-21; 0.5'-6'		
<b>Tested By:</b>	Thomas Wagner	<b>Date Tested:</b>	3/21/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>132</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>132</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
<b>Method:</b>	A
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 25; PI = 15  
Percent Retained on #4 Sieve = 3.2%; Percent Passing #200 Sieve = 54.8%

# Proctor Report

**Report No: PTR:W13-000494-S22****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S22	<b>Alternate Sample ID:</b>	LSS-22; 3'-15'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (14)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-22; 3'-15'		
<b>Tested By:</b>	Thomas Wagner	<b>Date Tested:</b>	3/21/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Optimum Moisture Content (%):</b>	<b>10</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>10</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 39; PI = 27  
Percent Retained on #4 Sieve = 3.4%; Percent Passing #200 = 63.0%

# Proctor Report

**Report No: PTR:W13-000494-S23****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S23	<b>Alternate Sample ID:</b>	LSS-23; 0.5'-15'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-7-6 (19)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-23; 0.5'-15'		
<b>Tested By:</b>	Shane Falwey	<b>Date Tested:</b>	3/21/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>127</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>127</b>
<b>Optimum Moisture Content (%):</b>	<b>11</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>11</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 44; PI = 31  
Percent Retained on #4 Sieve = 3.6%; Percent Passing #200 Sieve = 69.3%

# Proctor Report

**Report No: PTR:W13-000494-S24****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S24	<b>Alternate Sample ID:</b>	LSS-24; 2'-7'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Clayey Sand (SC); A-6 (3)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-24; 2'-7'		
<b>Tested By:</b>	Shane Falwey	<b>Date Tested:</b>	3/25/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>137</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>137</b>
<b>Optimum Moisture Content (%):</b>	<b>8</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>8</b>
<b>Method:</b>	D
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 26; PI = 13  
Percent Retained on #4 Sieve = 5.3%; Percent Passing #200 Sieve = 48.0%

# Proctor Report

**Report No: PTR:W13-000494-S25****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S25	<b>Alternate Sample ID:</b>	LSS-25; 0.5'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/14/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (14)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-25; 0.5'-10'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/26/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>129</b>
<b>Optimum Moisture Content (%):</b>	<b>10</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>10</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 40; PI = 27  
Percent Retained on #4 Sieve = 4.3%; Percent Passing #200 Sieve = 64.4%

# Proctor Report

**Report No: PTR:W13-000494-S26****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/5/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S26	<b>Alternate Sample ID:</b>	LSS-26; 0.5'-10'
<b>Date Sampled:</b>	3/12/2013	<b>Date Submitted:</b>	3/15/2013
<b>Sampled By:</b>	John Brooks	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (8)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-26; 0.5'-10'		
<b>Tested By:</b>	Kevin Ficek	<b>Date Tested:</b>	3/23/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>132</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>132</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
<b>Method:</b>	A
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 30; PI = 19  
Percent Retained on #4 Sieve = 2.7%; Percent Passing #200 Sieve = 60.7%



# Proctor Report

**Report No: PTR:W13-000494-S27****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S27	<b>Alternate Sample ID:</b>	LSS-027; 0.3'-5'
<b>Date Sampled:</b>	3/23/2013	<b>Date Submitted:</b>	3/23/2013
<b>Sampled By:</b>	Christopher Elliot	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (10)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-027; 0.3'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/8/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>123</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>123</b>
<b>Optimum Moisture Content (%):</b>	<b>11</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>11</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Dark Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 37, PI = 21  
Percent Retained on #4 Sieve = 4.6%, Percent Passing #200 Sieve = 59.6%



# Proctor Report

**Report No: PTR:W13-000494-S28****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S28	<b>Alternate Sample ID:</b>	LSS-028; 0.3'-10'
<b>Date Sampled:</b>	3/23/2013	<b>Date Submitted:</b>	3/23/2013
<b>Sampled By:</b>	Christopher Elliot	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-7-6 (17)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-028; 0.3'-10'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/8/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>122</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>122</b>
<b>Optimum Moisture Content (%):</b>	<b>12</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>12</b>
<b>Method:</b>	A
<b>Material on 19.0mm Sieve:</b>	Removed
<b>Rammer Type:</b>	Hand round
<b>Visual Description:</b>	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 44; PI = 30  
Percent Retained on #4 Sieve = 4.2%; Percent Passing #200 Sieve = 67.3%

# Proctor Report

**Report No: PTR:W13-000494-S29****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S29	<b>Alternate Sample ID:</b>	LSS-029; 0.3'-15'
<b>Date Sampled:</b>	3/23/2013	<b>Date Submitted:</b>	3/23/2013
<b>Sampled By:</b>	Christopher Elliot	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-7-6 (16)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-029; 0.3'-15'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/5/2013

## Dry Density - Moisture Content Relationship



## Test Results

\_\_\_\_ AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>123</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>123</b>
<b>Optimum Moisture Content (%):</b>	<b>11</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>11</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 41; PI = 27  
Percent Retained on #4 Sieve = 1.1%; Percent Passing #200 Sieve = 69.2%

# Proctor Report

**Report No: PTR:W13-000494-S30****Issue No: 1**

**Client:** Eric Bach  
SRF Consulting Group, Inc.  
Case Plaza  
Fargo, ND, 58102

**Project:** FA-12-00359  
Williston NW Bypass  
Several Routes, NW of Williston  
Williams County, ND, 58801

**PM:** Ezra Ballinger, eballinger@BraunIntertec.com



Brianne Nauman


EIT

Date of Issue: 4/9/2013

## Sample Details

<b>Sample ID:</b>	W13-000494-S30	<b>Alternate Sample ID:</b>	LSS-030; 0.3'-5'
<b>Date Sampled:</b>	3/23/2013	<b>Date Submitted:</b>	3/23/2013
<b>Sampled By:</b>	Christopher Elliot	<b>Sampling Method:</b>	Soil Boring Auger
<b>Source:</b>	Williston NW Bypass Subgrade		
<b>Material:</b>	Sandy Lean Clay (CL); A-6 (9)		
<b>Specification:</b>	For Informational Purposes Only		
<b>Location:</b>	LSS-030; 0.3'-5'		
<b>Tested By:</b>	Josh Beringer	<b>Date Tested:</b>	4/4/2013

## Dry Density - Moisture Content Relationship



## Test Results

AASHTO T 180 - 01

<b>Maximum Dry Density (lb/ft³):</b>	<b>126</b>
<b>Corrected Maximum Dry Density (lb/ft³):</b>	<b>126</b>
<b>Optimum Moisture Content (%):</b>	<b>9</b>
<b>Corrected Optimum Moisture Content (%):</b>	<b>9</b>
Method:	A
Material on 19.0mm Sieve:	Removed
Rammer Type:	Hand round
Visual Description:	Brown

## Comments

Assumed Specific Gravity = 2.75  
LL = 34; PI = 21  
Percent Retained on #4 Sieve = 2.5%; Percent Passing #200 Sieve = 60.4%